

TOM PALMER
UNION NATIONAL BANK BUILDING
WICHITA, KANSAS

15-163-00075-00-00

CASING RECORD

RUN	LEFT IN HOLE
20	
15 1/2	
12 1/2	
10	55'
8 1/4	
6 5/8	
5 3/16	

Location	SE-SW-NE of Sec. 17-8-16W		
Farm	H. H. Denio		
County	Rooks	State	Kansas
Contractor	The Palmer Oil Corporation		
Commence	10/31/40		
Completed	11/20/40		
Elevation	1821'		

FORMATION	REMARKS	FEET OF STRATA	TOTAL DEPTH
Cellar		8	8
Shale & gravel	(Reaming. Ran 50' of 10" pipe)	71	79
Shale	(Cemented with 25 sacks cement)	31	110
Shale & shells		508	618
Shale, shells, & pyrite		67	685
Sand		24	709
Shale & shells		41	750
Sand		50	800
Shale & Red Bed		125	925
Red Bed		173	1098
Shale, shells, & pyrite		27	1125
Shale		7	1132
Anhydrite		36	1168
Shale		197	1365
Shale, shells		105	1470
Shale		55	1525
Shale, shells		109	1634
Lime, anhydrite		8	1642
Anhydrite		24	1666
Lime		47	1713
Shale, lime		97	1808
Broken lime		65	1873
Lime		25	1898
Shale, lime		48	1946
Lime		179	2125
Shale		50	2175
Lime		50	2225
Shale, lime		65	2290
Lime		80	2370
Shale		160	2530
Shale, shells		38	2568
Lime		102	2670
Lime, shales		73	2743
Lime		317	3060
Shale		16	3076
Lime		261	3337
			TD

17 8
123 16W
14

Dry and abandoned.

State of Kansas)
County of Sedgwick) ss

Mr. Otto E. Schnepel, being first duly sworn on oath, states that he is the Secretary of The Palmer Oil Corporation, that as such officer, he is personally familiar with the records of The Palmer Oil Corporation, and that the above well log is a true, correct, and accurate copy of the original well log of Well #1, Denio farm, SE SW NE of Sec. 17-8-16W, Rooks County, Kansas.

Signed _____

Attest:
Subscribed and sworn before me this 30th day of November, 1940.

My Commission expires _____

Notary Public

12-5-40