

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-03901-00-00

API NUMBER N/A

LEASE NAME N. Chesney A

WELL NUMBER 3

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 18 TWP. 8-S RGE. 16 (E) or (W)

COUNTY Rooks

Date Well Completed 12-1-61

Plugging Commenced 8-20-90

Plugging Completed 8-20-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR S & M Oil Co.

ADDRESS 205 N. Jefferson; Plainville, KS 67663

PHONE# (913) 434-2829 OPERATORS LICENSE NO. 8735

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-20-90 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Kansas City Depth to Top 2728 Bottom 3168 T.D. 3205

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	LS	250	Surf	8 5/8	250	0
Kansas City	LS, SS, SH	3205	Surf	4 1/2	3205	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Plugged well down 2 3/8 tubing. Perforated at 1175'. Pumped 100 sacks 65-35 pos, 8% gel, 1/4 lb. floeal with 5 sacks hulls. Perforated 675', pumped 75 sacks, opened back side, circulated 25 sacks to surface, shut in back side, pumped 70 sacks at 750-800 PSI, perforated 200', circulated 30 sacks to surface, shut in well at 12:45 PM.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. N/A

Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: S & M Oil


STATE OF Kansas COUNTY OF Rooks, ss.

Steve Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Crawford

(Address) 205 N. Jefferson; Plainville, KS

Rec'd  
 9-21-90



SUBSCRIBED before me this 20th day of August, 19 90

Connie Newell  
 Notary Public

My Commission Expires: 4-9-94