

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,743-00-00

LEASE NAME Haines

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1 (SW-SW-NW)

2970
330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 27 TWP. 8S RGE. 16 (S) or (W)

COUNTY Rooks

Date Well Completed Oct. 24, 1977

Plugging Commenced Oct. 17, 1985

Plugging Completed _____

LEASE OPERATOR ENERGY EXPLORATION & PROD. INC.

ADDRESS 5501 Foxridge Drive
Mission, Kansas 66202

PHONE# (913) 722-5955 OPERATORS LICENSE NO. 5639

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Unknown if not, is well log attached? Geological Report & Electrical Log Attached

Producing Formation Kansas City Depth to Top 3,080 Bottom 3286 T.D. 3320'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	208	8 5/8"	208'	None
		0	3320	4 1/2"	3319'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Per instructions from Dennis Hamel, Plainville, Kansas Dist. #6, Halliburton Services Pumped 25 Sacks Cement followed by 15 sacks Gel, followed by 125 sacks cement with Hulls throughout. Between 4 1/2" casing and 8 5/8" surface Pipe, pumped 50 sacks cement followed by 15 sacks Gel, followed by 50 sacks cement with Hulls throughout.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services, Hays, Kansas License No. _____

Address _____

STATE OF Kansas COUNTY OF Harvey, ss.

Clay Hedrick, Jr.


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Clay E. Hedrick, Jr.

(Address) Box 346 Newton, Kansas 67114

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 19 85



Commission Expires: Feb. 17, 1987

Notary Public
RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1985
11-1-85
Form CP-4
Revised 08-84
CONSERVATION DIVISION
Wichita, Kansas