


15-163-00413-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks

County. Sec. 18 Twp. 8S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SW

Lease Owner Herndon Drilling Company

Lease Name Chesney Well No. 1

Office Address 423 Mayo Building - Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed June 15 19 55

Application for plugging approved June 17 19 55

Plugging commenced June 21 19 55

Plugging completed June 24 19 55

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3087' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	None
				5-1/2"	3087'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 3087' to 3030' and ran 4 sacks of cement. Mudded the hole to 310', set a 10' rock bridge and ran 5 sacks of cement on top. Mudded the hole to 40' and ran 5 sacks of cement on top. Plugging compl.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 9 - 1955

CONSERVATION DIVISION  
WICHITA, KANSAS

Name of Plugging Contractor West Supply Company (If additional description is necessary, use BACK of this sheet) 7-9-55  
Address Chase, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss. J. D. Chew

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. Chew

SUBSCRIBED AND SWORN TO before me this 8th day of July 19 55 (Address)

My commission expires Sept 19, 1956 Notary Public.

PLUGGING  
FILE SEC 18 T 8 R 16W  
BOOK PAGE 127 LINE 17

15-163-00413-00-00

WELL LOG ON CRISTAL #1

Spudding date: 4/28/52  
Date casing set: 5/11/52  
Date rotary completed: 5/16/52  
Date cable completed:

Location: Section 15, T-12N, R-10E, Kansas  
County, Kansas

FROM	TO	FORMATION	REMARKS
0	40	Surface	
0	250	Shale	Run 8 lbs of 5-5/8" casp.
0	500	Shale & shells	Set @ 250', Cemented 1/150
0	540	Sand	and. of cement.
0	800	Sand and shale	
1055	1205	Shale and shells	
1205	2205	Shale and lime	
2205	2840	Sand and lime	
2840	3067	Lime and shale	
3067		TOTAL DEPTH	Run 122 lbs. of 5" casp.
			Set @ 3067', Cemented 1/100
			and. of cement.

RECEIVED  
STATE COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

7-9-55

Subscribed and sworn to before me this 13th day of July, 1952

I certify the above and foregoing to be a true and exact copy of the original driller's log on the CRISTAL #1

E. J. Dargatzis  
Notary Public  
My commission expires:  
My commission expires Aug. 28, 1953

HEERDON DRILLING COMPANY  
By: C. J. Moore  
Title:

PLUGGING  
MAX SIC 18 8 1/6 W  
BOOK PAGE 127 LINE 17