

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

~~15-163-30020-00-00~~

15-163-02979-00-01

API NUMBER N/A

LEASE NAME N. Chesney D

WELL NUMBER 1

2970 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 18 TWP. 8-S GE. 16 (X) or (W)

COUNTY Rooks

Date Well Completed 7-18-52

Plugging Commenced 7-31-90

Plugging Completed 7-31-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR S & M Oil Co.

ADDRESS 205 N. Jefferson, Plainville, KS 67663

PHONE#(913) 434-2829 OPERATORS LICENSE NO. 8735

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-30-90 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation none Depth to Top -- Bottom -- T.D. 1180
Anhydrite top was 1130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	ss, ls, sh	1130	surf	8 5/8	1130	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran 2" tubing to 1180' & circulated cement back to surface with 3 sks. hulls mixed with 210 sks 65/35 pos, 8% gel, 1/4 lb. flo-seal. Pulled tubing. Tied onto 8 5/8 casing, mixed 40 sks. 65/35 pos, 8% gel, 1/4 lb. flo-seal at 500# max. pressure and shut in at 300#.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. N/A

Address Russell, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: S & M Oil Co.

STATE OF Kansas COUNTY OF Rooks, ss.

Steve Crawford (Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Crawford

(Address) 205 N. Jefferson, Plainville, Ks

SUBSCRIBED AND SWORN TO before me this 31 day of July, 19 90

Connie Newell
 Notary Public



mission Expires: 4-9-94

RECEIVED
 STATE CORPORATION COMMISSION

AUG 2 1990
 8-2-90

CONSERVATION DIVISION of
 WICHITA, KANSAS