

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-20,480-00-00

LEASE NAME N. Chesney D

WELL NUMBER 2

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 18 TWP. 8-S RGE. 16-W E or (W)

COUNTY Rooks

Date Well Completed 12-17-72

Plugging Commenced 8-13-90

Plugging Completed 8-13-90

LEASE OPERATOR S & M Oil Co.

ADDRESS 205 N. Jefferson; Plainville, KS

PHONE# (913) 434-2829 OPERATORS LICENSE NO. 8735

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-13-90 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? to CP-1 form

Producing Formation KC Depth to Top 2942 Bottom 3126 T.D. 3130

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	SS, LS, SH	1129	surf	8 5/8	1129	0
KC	LS, SH	3130	surf	5 1/2	3140	1725

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. sand off perforations & cap sand with 5 sacks cement. Cut off 5 1/2" casing at 1725' & cement 8 5/8 with 225 sacks of 65/35 pos., 10% gel, 1/4 lb. floeal per sack & 1 sack hulls. Cemented at 1000 lbs. and shut in at 800 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. N/A

Address Russell, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: S & M Oil; Plainville, KS.

STATE OF Kansas COUNTY OF Rooks, ss.

Steve Crawford (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Crawford

(Address) 205 N. Jefferson; Plainville, KS



AND SWORN TO before me this 13<sup>th</sup> day of August, 19 90

Connie Newell  
 Notary Public

My Commission Expires: 4-9-94