

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-065-22,679 000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Ainsworth Operating Company OPERATOR'S LICENSE NO. 6030

ADDRESS P.O. Box 1269, Colorado Springs, CO 80901 PHONE # (719) 576-5300

LEASE (FARM) Hale WELL NO. #1 WELL LOCATION SW NW NE COUNTY Graham

SEC. 12 TWP. 7S RGE. 23 (E) or (W) TOTAL DEPTH 3840' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 259' CEMENTED WITH 60-40 posmix-185 sx SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2038' w/25 sx; 2nd plug @

1220' w/100 sx; 3rd plug @ 300' w/40 sx; 4th plug @ 40' w/wiper plug w/10 sx; rathole 15

sx; 60-40 posmix 6% gel 1/4# floccel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No
(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5:30 p.m. 5-24-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 743-8443

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684

ADDRESS 150 N. Main, suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: July 1, 1992

RECEIVED
7/6/92
JUL 6 1992
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas