

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,679 0000

LEASE NAME Hale

WELL NUMBER #1

4290' Ft. from S Section Line

1650' Ft. from E Section Line

SEC. 12 TWP. 7S RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 5-24-92

Plugging Completed 5-25-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ainsworth Operating Company

ADDRESS P.O. Box 1269, Colorado Springs, CO 80901

PHONE# (719) 576-5300 OPERATORS LICENSE NO. 6030

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-25-92 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation LKC Depth to Top _____ Bottom _____ T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	259'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill w/heavy mud; set 1st plug @ 2038'-1935' w/25 sx; 2nd plug @ 1220'-820' w/100 sx; 3rd plug @ 300'-140' w/40 sx; 4th plug @ 40'-surface w/10 sx w/wiper plug; rathole 15 sx; 60-40 posmix 6% gel 1/4# Flocel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684


Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ainsworth Operating Company

STATE OF Kansas COUNTY OF Sedgwick, ss. STATE CORPORATION COMMISSION

Jack K. Wharton

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack K. Wharton RECEIVED
7/16/92
JUL 6 1992
CONSERVATION DIVISION
Wichita, Kansas

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 15 day of July, 19 92

My Commission Expires: March 20, 1993
Angela Woodard
Notary Public