


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 16 Twp. 7 Rge. 23 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C-SW&NW
Lease Owner Woodman & Iannitti Drilling Co.
Lease Name Brant Well No. 1
Office Address P. O. Box 387, Hoisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 6-27 19 59
Application for plugging filed 6-19 19 59
Application for plugging approved 6-19 19 59
Plugging commenced 6-19 19 59
Plugging completed 6-27 19 59
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	170'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran Welex Log
Bottom Plug 550' 20 sacks
Middle Plug 170' 20 sacks
Top Plug 40' 10 sacks

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1959
CONSERVATION DIVISION
Wichita, Kansas
6/30/59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Iannitti Drilling Co.
Address P. O. Box 387, Hoisington, Kansas

STATE OF _____, COUNTY OF _____, ss. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1959

My commission expires May 13, 1962
Virginia H. Dodge Notary Public.

PLUGGING
FILE SEC 16 T 7 R 23W
BOOK PAGE 49 LINE 11

~~6/30/59~~DRILLING LOG

Company: Woodman & Iannitti Drilling Co.
 Lease: #1 Brant C-SW-NW 16-7-23W
 Graham County, Kansas
 Contractor: Woodman & Iannitti Drilling Co.
 Box 387, Hoisington, Kansas
 Date Commenced: 6-19-59
 Date Completed: 6-27-59
 Total Depth: 3900'
 Casing: 8 5/8" set at 170' with 130 sacks quick-set
 cement.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 30 1959
 CONSERVATION DIVISION
 Wichita, Kansas
 6/30/59

Figures Indicate the Bottom of the Formation

0- 50	Sand Post Rock	2185-2395	Shale & Shells
75	Sand	2520	Lime
135	Sand Clay	2675	Lime
170	Blue Shale	2785	Lime
950	Shale	2890	Lime
1580	Shale & Sand	3025	Lime
1840	Sand	3120	Lime
1960	Shale Red Bed	3195	Lime
2095	Red Bed	3285	Lime & Shale
2130	Anhydrite	3350	Lime
2185	Shale & Shells	3430	Lime
		3530	Lime
		3900	Lime

GEOLOGICAL TOPS

Elevation	2395 RB
Anhydrite	2090 /305
Heebner	3642 -1247
Toronto	3667 -1272
Lansing	3681 -1286
B/Kansas City	3873 -1478
Total Depth	3900 -1505

I certify the above to be a true and correct copy of the Driller's log and the Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
 K. T. Woodman

PLUGGING
 FILE SEC 16 T 7 R 23W
 BOOK PAGE 48 LINE 11