

15-065-21322-0000  
 STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

RECEIVED Form CP-4  
 STATE CORPORATION COMMISSION REVISION 12-15-80  
 OCT 15 1982 10/15/82  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Graham SEC. 13 TWP. 7 RGE. 23W E/W  
 Location as in quarters or footage from lines:


Locate Well  
 correctly on above  
 Section Platt.

SE NE NW  
 Lease Owner Rains & Williamson Oil Co., Inc.  
 Lease Name Robinson #1 Well No. \_\_\_\_\_  
 Office Address 435 Page Court Bldg, 220 W. Douglas Wichita, Ks.  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 9-29-82  
 Plugging completed 10-5-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted \_\_\_\_\_  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	273'	none
				4-1/2"	3839'	1634'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Pumped bottom with 30 sacks cement and plug stopped @3300'. Shot casing @3300', 2996', 2700', 2452', 2036', 1837', 1630', pulled a total of 40 joints of 4-1/2" casing. Plugged well with 2 sacks hulls, 27 sacks gel, 70 sacks cement, 13 sacks gel, released plug and displaced with 70 sacks cement.~~

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1982

My Commission expires: \_\_\_\_\_



Irene Hoover  
 Notary Public.

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 13 T. 7S R. 23W

LOC. SE NE NW

WELL NAME: Robinson #1

COUNTY: Graham

RIG NO. #4

TOTAL DEPTH 3840'

ELEVATION 2339 GL 2344 KE

COMMENCED: 11-7-80

COMPLETED: 11-16-80

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 273' w/85 sx. 60/40 poz., 3% cc., 2% gel.

PRODUCTION: 4 1/2" @ 3839' w/150 sx. 60/40 poz., 2% gel, 10 bbl. saltflush

LOG

(Figures Indicate Bottom of Formations)

Clay, Sand & Shale	282
Shale & Sand	1997
Shale	3135
Shale & Lime	3455
Lime & Shale	3605
Lime	3680
Shale & Lime	3820
Lime & Shale	3840
<u>ROTARY TOTAL DEPTH</u>	<u>3840</u>

STATE OF Kansas )

COUNTY OF Sedgwick )


SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the Robinson #1 well.

*Received:*  
*1-10-1981*

*Wilson Rains*  
Wilson Rains



Subscribed and sworn to before me this 9 day of January, 1981.

My Appointment Expires: 10-4-83

*Juanita M. Green*  
Juanita M. Green