

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas


15-065-00132-00-00
WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Graham County. Sec. 17 Twp. 7 Rge. (E) 23 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW SW NW
Lease Owner. Jones Shelburne & Farmer
Lease Name. J. S. Barrow Well No. 1
Office Address. Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole
Date well completed. Aug. 25 19 50
Application for plugging filed. Aug. 25 19 50
Application for plugging approved. Aug. 25 19 50
Plugging commenced. Aug. 25 19 50
Plugging completed. Aug. 25 19 50
Reason for abandonment of well or producing formation. Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production No 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough
Producing formation. Depth to top. Bottom. Total Depth of Well. 4183 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	180	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole Loaded with Heavy Mud

15 sax Cement set @ 170 feet Bottom Plug

10 sax Cement set @ 35 feet Top Plug

9/15/50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Iron Drilling Company
Address 1206 Philtower Bldg., Tulsa, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

J. L. Stackpole (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.


(Signature) J. L. Stackpole

SUBSCRIBED AND SWORN to before me this 11th day of September, 19 50

(Address) J. Michal

My commission expires Feb. 28, 1952

Notary Public.



15-aes-00132-cw-00

DRILLING RECORD

Well No. 1 J. S. Barrow
Located SW SW NW in Sec. 17-7S-23W
Graham County, Kansas

Casing

180' of 8-5/8" OD Surface
Pipe cemented with 75 sacks

No Oil String - Dry Hole

Work Commenced 8/9/50
Drilling Commenced 8/10/50
Drilling Completed 8/24/50
Work Completed 8/25/50

WELL LOG

Clay & Shells	0 to 78
Sand	78 to 100
Clay & Shells	100 to 180
Sand & Shale	180 to 417
Sand & Gumbo	417 to 910
Shale & Shells	910 to 990
Shale & Sand	990 to 1595
Red Rock & Shale	1595 to 1695
Sand & Red Bed	1695 to 1890
Shale & Red Bed	1890 to 2120
Cherty Lime	2120 to 2142
Anhydrite	2142 to 2160
Shale & Shells	2160 to 2684
Lime	2684 to 2717
Shale & Shells	2717 to 2800
Lime	2800 to 2978
Brown Sandy Lime	2978 to 2991
Lime & Shale	2991 to 3070
Shale & Shells	3070 to 3160
Shale	3160 to 3242
Lime & Shale	3242 to 3280
Shale & Shells	3280 to 3323
Lime	3323 to 3468
Shale & Lime	3468 to 3488
Lime	3488 to 3670
Lime & Shale	3670 to 3693
K. C. Lime	3693 to 3714
Lime	3714 to 3957
Shale & Lime	3957 to 4078
Shale & Chert	4078 to 4123
Lime & Chert	4123 to 4165
Shale & Lime	4165 to 4175
Shale, Lime & Chert	4175 to 4183 TD

RECORDED

SEP 15 1950

9/15/50

PLUGGING
 FILE SEC 17 7 23W
 ROCK FACE 76 LINE 10