

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: FIML Natural Resources, LLC
Address: 410 - 17th Street, Suite 900, Denver, CO 80202
Phone: (303) 899-5608 Operator License #: 33476
Type of Well: D&A Docket #:
The plugging proposal was approved on: 12/31/05
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
NA Depth to Top: Bottom: T.D.

API Number: 15 - 163-23488-0000
Lease Name: Conyac
Well Number: 3A-19-818
Spot Location (QQQQ): - NE - NE - NW
330 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 19 Twp. 8 S. R. 18 East West
County: Rooks
Date Well Completed: 12/31/05
Plugging Commenced: 12/31/05
Plugging Completed: 12/31/05

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Arbuckle 3252-3303', Wet, Surface, 309', 8-5/8", 309', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 6 cement plugs containing 210 sx 60/40 Poz, 6% gel, 0.25 pps flocele, 12.4 ppg, 1.5 cuft/sx. Plug 1- 25 sx at 3500-3389'.

Plug 2- 25 sx at 1475-1364'. Plug 3- 100 sx at 975-531'. Plug 4- 40 sx at 350-172'. Plug 5- 10 sx at 40'-surface.

Plug 6- 10 sx at 45'-surface (rathole).

Name of Plugging Contractor: Forrest Energy LLC License #: 33436
Address: 410 Urban Drive, Hutchinson, KS 67501

Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC
State of Colorado County, Denver, ss.

Phyllis Sobotik (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Phyllis Sobotik
(Address) 410 17th Street, Suite 900, Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 8th day of February, 2006
Notary Public My Commission Expires: 5/5/2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED FEB 13 2006 KCC WICHITA

Handwritten signature/initials.