

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Heartland Oil & Gas Corporation
Address: 1610 Industrial Park Drive Paola KS 66071
Phone: (913) 294-1400 Operator License #: 33233
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-07-05 (Date)
by: Taylor Herman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 1875 Bottom: 2200 T.D. 2412
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-085-20074-00-00
Lease Name: Amon
Well Number: 15-15
Spot Location (QQQQ): SW-NE-SW-SE 2-13-06 ROOMS
810 Feet from North / South Section Line
1830 Feet from East / West Section Line
Sec. 15 Twp. 5 S. R. 15 East West
County: Jackson
Date Well Completed: 9-01-04
Plugging Commenced: 1-23-06
Plugging Completed: 1-25-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	250'	8 5/8	250'	None
	Production	GL	2377.5'	5 1/2	2377.5'	1022'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 1-23-06, tagged at 2277' and pulled tubing to 2262'. Pumped 39 bbls of gelled water and pumped 35 sx of Class A cement with 1 sx of cottonseed hulls. Displaced with 7.5 bbls of gelled water. Had gel from 298' to 1955' and cement from 1955' to 2262'.

On 1-25-06, shot casing at 1022', pulled to 310', loaded hole and mixed and pumped 90 sx of Class A cement. Circulated cement to surface and pulled casing.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006 **RECEIVED KANSAS CORPORATION COMMISSION**
Address: PO Box 782228 Wichita KS 67278-2228
Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc. *Connect Per Oper Mish Kuttell*
State of Kansas County, Sedgwick, ss. 2-21-06 *BEM KCC* **FEB 1 2006 CONSERVATION DIVISION WICHITA, KS**
Darrel G. Walters (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 782228 Wichita KS 67278-2228

SUBSCRIBED and SWORN TO before me this 13th day of February, 2006

[Signature] My Commission Expires: 12-21-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

12-21-07

Bem