

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Heartland Oil & Gas Corporation
Address: 1610 Industrial Park Drive Paola KS 66071
Phone: (913) 294-1400 Operator License #: 33233
Type of Well: SWD Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-28-05 (Date)
by: Taylor Herman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Open hole Depth to Top: 4076 Bottom: 4183 T.D. 4183

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-131-20184-00-00
Lease Name: Georg
Well Number: 15-12 WD *KCC BEM 2-13-06*
Spot Location (QQQQ): _____ - _____ - SW - SE R0Dms
580 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 12 Twp. 3 S. R. 14 East West
County: Nemaha
Date Well Completed: 7-14-04
Plugging Commenced: 1-16-06
Plugging Completed: 1-19-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	283'	8 5/8	283'	None
	Production	GL	4076'	5 1/2	4076'	818'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 1-16-06, ran tubing and tagged at 4180'. Pumped 80 bbls of gelled water but hole did not load. Mixed and pumped 50 sx of Class A cement plus 2 sx of cottonseed hulls. Displaced with 14.5 bbls plus 1 sx of cottonseed hulls. Pulled tubing to 3607' and waited for 1 hr. Ran tubing to 3702 and pumped 81 bbls of gelled water. Pulled tubing and shot casing at 818'. Had cement from 3723' to 4180' and gelled water from 300' to 3702'. On 1-19-06, pulled casing to 292' and pumped 85 sx of Class A cement, circulated cement to surface and pulled casing.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006 **RECEIVED**
Address: PO Box 782228 Wichita KS 67278-2228 **KANSAS CORPORATION COMMISSION**

Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc. *Consent Per Operator* **FEB 13 2006**
State of Kansas County, Sedgwick, ss. 2-21-06 BEM *KCC* **CONSERVATION DIVISION WICHITA, KS**
Darrel G. Walters (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 782228 Wichita KS 67278-2228

SUBSCRIBED and SWORN TO before me this 13th day of February, 2006

[Signature] My Commission Expires: 12-21-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 *12-21-07*