

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
FEB 13 2006
KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Merit Energy Company
Address: 13727 Noel Rd. Suite 500 Dallas, Texas 75240
Phone: (214) 686-2312 Operator License #: 32446
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: November 7, 2005 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lower Morrow Depth to Top: 6362' Bottom: 6408' T.D. 7010'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-189-22467-00-00
Lease Name: KU Endowment "C"
Well Number: 4
Spot Location (QQQQ): _____ - CW/2 - SW - SE
660 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 35 Twp. 34 S. R. 38 East West
County: Stevens
Date Well Completed: 05/03/04
Plugging Commenced: 01/25/06
Plugging Completed: 01/27/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chase		0'	1759'	8-5/8"	1759'	0'
Council Grove		0'	6995'	5-1/2"	6995'	2485'
Morrow						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 6300' w/2 sxs. cmt. on top. RIH & cut 5-1/2" csg. @ 2485'. Spot 30 sx. cmt. plug from 2485' - 2385'. Spot 50 sx. cmt. plug from 1780' - 1680'. Spot 40 sx. cmt. plug from 600' - 500'. Spot 15 sx. cmt. plug from 40' to surface. Dig out & cut off surface csg. 4' below GL. Weld on identification plate.

Name of Plugging Contractor: Eagle Well Service License #: 7407
Address: 936 Ulysses Parkway Ulysses, Kansas 67880

Name of Party Responsible for Plugging Fees: Merit Energy Company
State of Texas County, Dallas, ss.

Lynne Moon (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Lynne Moon
(Address) 13727 Noel Rd. Suite 500 Dallas, Texas 75240

SUBSCRIBED and SWORN TO before me this 9th day of February
Elizabeth L. Lyon My Commission Expires _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

bm