

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
FEB 13 2006
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Merit Energy Company
Address: 13727 Noel Rd. Suite 500 Dallas, Texas 75240
Phone: (972) 628-1569 Operator License #: 32446
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 09/27/05 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Chester Depth to Top: 5648' Bottom: 5656' T.D. 6150'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-187-21044-0000
Lease Name: Lucas "A"
Well Number: 1
Spot Location (QQQQ): NW - SW - SE - SE
618 Feet from North / South Section Line
1200 Feet from East / West Section Line
Sec. 35 Twp. 30 S. R. 39 East West
County: Stanton
Date Well Completed: 09/22/04
Plugging Commenced: 01/28/06
Plugging Completed: 01/30/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chase		0'	1776'	8-5/8"	1776'	0'
Council Grove		0'	5889'	5-1/2"	5889'	2400'
Morrow						
Chester						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 5600' w/2 sx. cmt. on top. Cut 5-1/2" csg. @ 2400'. Pump 30 sx. cmt. plug 2400' - 2300'. Pump 50 sx. cmt. plug from 1800 - 1650'.
Pump 40 sx. cmt. plug from 550' - 450'. Pump 20 sx. cmt. plug from 60' to surface. Dig out & cut off surface csg. 4' below
GL. Welded on identification plate.


Name of Plugging Contractor: Eagle Well Sevice License #: 7407
Address: 936 Ulysses Parkway Ulysses, Kansas 67880

Name of Party Responsible for Plugging Fees: Merit Energy Company
State of Texas County, Dallas, ss.

Lynne Moon (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Lynne Moon
(Address) 13727 Noel Rd. Suite 500 Dallas, Texas 75240

SUBSCRIBED and SWORN TO before me this 9th day of February, 2006
Elizabeth L. Lyon My Commission Expires 10-31-09
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202