

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

FEB 16 2006

KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
Address: P. O. Box 399, Garden City, KS 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/17/2005 (Date)
by: Eric Mac Cleren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 5137 Bottom: 5133 T.D. 5742

Depth to Top: 5114 Bottom: 5118 T.D. 5742

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 025-20,264 - 00-00
Lease Name: V.W. Harmon
Well Number: 1
Spot Location (QQQQ): SE - NW NW - 2116/06 RBDM 3 CP 2/3
4290 Feet from North / South Section Line
4290 Feet from East / West Section Line
Sec. 11 Twp. 35 S. R. 22 East West
County: Clark
Date Well Completed: 3/14/1979
Plugging Commenced: 12/14/2005
Plugging Completed: 12/16/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	650	None
				5 1/2	5796	3150

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


12/14 - set CIBP at 5660', spot 2 sacks cement with dump bailer, call out welder, split casing head 12/15 - stretch and cut pipe at 3150'
12/16 - pull casing to 1050', Allied load hole with 10 sacks gel, pump 50 sacks 60/40 poz 6% gel, pull casing to 680', pump 50 sacks, pull 300', pump 40 sacks, pull to 40', pump 10 sacks to surface, top off 1/2 yard redi-mix

Name of Plugging Contractor: Clarke Corporation License #: 5105
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 10 day of February, 20 06
Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DM