

RECEIVED

FEB 16 2006

Form CP-4
December 2003

Print on this Form

Form must be Signed

All blanks must be Filled

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: Downing - Nelson Oil Company, Inc.

Address: P.O. Box 372, Hays KS 67601

Phone: (785) 621-2610 Operator License #: 30717

Type of Well: Gas DH Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/22/2005 (Date)

by: Greg Egef (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: 4320 Bottom: 4326 T.D. 4330

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 095-21-982-00-00

Lease Name: Hawley

Well Number: 2-16

Spot Location (QQQQ): NWSE sw/4 - _____ - _____
990 Feet from North / South Section Line

1710 Feet from East / West Section Line

Sec. 16 Twp. 30 S. R. 9 East West

County: Kingman

Date Well Completed: 9/20/2005

Plugging Commenced: 11/23/2005

Plugging Completed: 11/29/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	220	None
				5 1/2	4498	3800

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

11/23 - set CIBP at 4270', spot 2 sacks cement with dump bailer, stretch and cut pipe at 3800'
11/28 - pull pipe free, shut down due to windy conditions
11/29 - pull casing to 1400', Allied load hole with 15 sacks gel, pump 35 sacks 60/40 poz 6% gel, pull casing to 950', pump 35 sacks, pull 270', pump 35 sacks, pull to 40', load to surface

Name of Plugging Contractor: Clarke Corporation License #: 5105


Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Downing - Nelson Oil Company, Inc.

State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 10 day of February, 20 06

Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC
BEM
2-16-06
RBDMS
CP 2/3
Dist

KCC
BEM
2-16-06
RBDMS
CP 2/3
Dist

Bm