

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

API NUMBER 15-067-00080-0000

LEASE NAME ELDRIDGE

WELL NUMBER 1-26

2540' FSL Ft. from S Section Line

2540' FEL Ft. from E Section Line

SEC. 26 TWP. 29S RGE. 35W (E) or (W)

COUNTY GRANT

Date Well Completed 03/27/44

Plugging Commenced 02/01/06

Plugging Completed 02/02/06

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/28/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3012' Bottom 2750' T.D. 2750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2526'	2747'	10 3/4"	654'	0'
				7"	2518'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

2/1-2/06 Witnessed by J Holland, KCC. Set CIBP @2350' KB, spot 10' cmt. Revise PBTD @2340'. NU cmtr to 7" csg, pmp 18 bbl mud to 1800' & 40 sx cmt 1800'-1600' & 65 bbl mud to 0'. NU cmtr to 7" csg, load & circ hole w/55 bbl mud & 75 sx cmt 660'--510'. Displ w/17 bbl mud, load hole to 40' w/8 bbl mud, pmp 15 sx cmt 40'-0'. Cut 7" & 10 3/4" csg 3' bgl, weld on trash cover - ID plate

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039


SUBSCRIBED AND SWORN TO before me this 14th day of February, 20 06

My Commission Expires: 3/27/06

Notary Public

RECEIVED
FEB 16 2006
KCC WICHITA

USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88

Bm