

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED FEB 16 2006 KCC WICHITA Form CP-4 December 2003 or Print on this Form Form must be Signed Blank must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. Box 399, Garden City, KS 67846

Phone: (620) 275-2963 Operator License #: 4058

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/14/2005 (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: 5721 Bottom: 5727 T.D. 5731
Depth to Top: 5717 Bottom: 5719 T.D. 5731
Depth to Top: 5710 Bottom: 5714 T.D. 5731

API Number: 15-025-20,358-00-00

Lease Name: Barth

Well Number: 1-A

Spot Location (QQQQ): NW - 2-21-06 R80ms

3960 Feet from North / South Section Line

3960 Feet from East / West Section Line

Sec. 10 Twp. 35 S. R. 22 East West

County: Clark

Date Well Completed: 3/14/1979

Plugging Commenced: 12/19/2005

Plugging Completed: 12/23/2005

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

12/14-CIBP stack out 3600' move off 12/19-MIRU, run tubing to 3600' with notched collar, stacked, try to rotate through try to circulate through with Allied, could not circulate, pull tubing, collar bent, 12-20-run tubing to 3540', circulate, run 150 hulls, pump 45 sacks class a with 50 hulls, pump 25 sacks with 3% CC displace 9 1/2 bbls., pull 1500' tubing, 12/21-run tubing, tag at 2717', pull tubing, stretch pipe 12/22-stretch and cut casing at 2550', pull casing to 1100', 12/23-Allied load hole at 1100' with 10 sacks gel, 40 sacks 60/40 poz, 6% gel, OVER ->

Name of Plugging Contractor: Clarke Corporation License #: 5105


Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 10 day of February, 20 06

Glenda Morrison My Commission Expires: 11/30/06 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pull pipe to 860', pump 50sx, pull to 400'. Pump 40sx5, pull to 40'. Load to surface, plug dropped, top off 2 1/2 yards red mix