

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-20749-0000

LEASE NAME JARVIS

WELL NUMBER 4-36

1350' FNL Ft. from S Section Line

1250' FWL Ft. from E Section Line

SEC. 36 TWP. 30S RGE. 38W (E) or (W)

COUNTY GRANT

Date Well Completed 05/26/88

Plugging Commenced 02/03/06

Plugging Completed 02/03/06

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/28/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3137' Bottom 2908' T.D. 3000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2460'	2778'	8 5/8"	713'	0'
				5 1/2"	2999'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

2/3/06 Witnessed by J Holland, KCC. Set CIBP @2410' KB, spot 20' cmt, Revise PBTD @2390'. NU cmtr to 5 1/2" csq, load hole w/15 bbl mud to 1750' & 20 sx cmt plug frm 1750'-1550' & 14 bbl mud 1550'-750' & 20 sx cmt plug 750'-550' & 11 bbl mud 550'-100' & 10 sx cmt plug 100'-0'. Cut 8 5/8" surf csq & 5 1/2" csq @ 3' bgl, weld on trash cover-ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1. BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



AND SWORN TO before me this 13th day of February, 20 06

My Commission Expires: 4/2/09 Deborah Pollock Notary Public

Bum