

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Heartland Oil & Gas Corporation
 Address: 1610 Industrial Park Drive Paola KS 66071
 Phone: (913) 294-1400 Operator License #: 33233
 Type of Well: Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 11-28-05 (Date)
 by: Taylor Herman (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: 2054 Bottom: 2507 T.D. 2675
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-131-20186-00-00
 Lease Name: Mauersberger
 Well Number: 15-14
 Spot Location (QQQQ): SE - NW - SW - SE
810 Feet from North / South Section Line
2130 Feet from East / West Section Line
 Sec. 14 Twp. 4 S. R. 14 East West
 County: Nemaha
 Date Well Completed: 8-10-04
 Plugging Commenced: 1-05-06
 Plugging Completed: 1-09-06

*KCC
BEM
2-13-06
KBDMS*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	281.3'	8 5/8	281.3'	None
	Production	GL	2659.8	5 1/2	2659.8	1105'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 1-05-06, ran tubing and tagged at 2557'. Pumped 40 bbls of water and 65 sx of Class A cement with 1 sx of cottonseed hulls. Cement was from 1990' to 2551' and gel from 300' to 1990'. On 1-09-06, shot casing at 1105' and pulled casing to 299'. Loaded hole and mixed and pumped 85 sx of Class A cement. Circulated cement to surface and pulled casing.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006 **RECEIVED KANSAS CORPORATION COMMISSION**
 Address: PO Box 782228 Wichita KS 67278-2228 **FEB 13 2006**
 Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc. *Consent Per Oper* *Mish Wittell*
 State of Kansas County, Sedgwick, ss. *2-21-06 BEM KCC* **CONSERVATION DIVISION WICHITA, KS**
 Darrel G. Walters (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *[Signature]*

(Address) PO Box 782228 Wichita KS 67278-2228

SUBSCRIBED and SWORN TO before me this 13th day of February, 2006

[Signature] My Commission Expires: 12-21-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
 LYLIA M. CLARK My Appt. Exp. 12-21-07

BEM