

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: Heartland Oil & Gas Corporation

Address: 1610 Industrial Park Drive Paola KS 66071

Phone: (913) 294-1400 Operator License #: 33233

Type of Well: Gas Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*

The plugging proposal was approved on: 11-30-05 (Date)

by: Taylor Herman (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (if needed attach another sheet)

_____	Depth to Top: <u>2318</u>	Bottom: <u>2475</u>	T.D. <u>2720</u>
_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____

API Number: 15-131-20181-00-00

Lease Name: Renyer

Well Number: 14-12

Spot Location (QQQQ): SW - NE - SE - SW  
810 Feet from  North /  South Section Line  
3150 Feet from  East /  West Section Line

Sec. 12 Twp. 3 S. R. 14  East  West

County: Nemaha

Date Well Completed: 8-06-04

Plugging Commenced: 1-10-06

Plugging Completed: 1-12-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	282.4'	8 5/8	282.4'	None
	Production	GL	2703.4'	5 1/2	2703.4'	1078'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 1-10-06, ran tubing and tagged at 2598'. Spotted 2 bbls of gelled water (Had gel from 2525' to 2598'). Pulled tubing to 2525' and pumped 45 bbls of gelled water and spotted 35 sx of Class A cement plus 1 sx of cottonseed hulls. Displaced with 8.5 bbls of gelled water (Gel from 2219' to 300' and cement from 2219' to 2525'). On 1-12-06, shot casing at 1078' and pulled to 297'. Mixed and pumped 85 sx of Class A cement, circulated cement to surface and pulled casing.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006

Address: PO Box 782228 Wichita KS 67278-2228

Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc.

State of Kansas County, Sedgwick, ss. \_\_\_\_\_

Darrel G. Walters

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) PO Box 782228 Wichita KS 67278-2228

SUBSCRIBED and SWORN TO before me this 13<sup>th</sup> day of February, 2006

Lillian M. Clark  
Notary Public

My Commission Expires: 12-21-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED**  
**KANSAS CORPORATION COMMISSION**  
**FEB 13 2006**  
**CONSERVATION DIVISION**  
**WICHITA, KS**

LYLIA M. CLARK  
My Appl. Exp. 12-21-07

*Bem*