

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Heartland Oil & Gas Corporation
 Address: 1610 Industrial Park Drive Paola KS 66071
 Phone: (913) 294-1400 Operator License #: 33233
 Type of Well: Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 11-30-05 (Date)
 by: Taylor Herman (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
 _____ Depth to Top: 2351 Bottom: 2485 T.D. 2760
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-131-20180-00-00
 Lease Name: Georg
 Well Number: 16-12
 Spot Location (QQQQ): SE - NW - SE - SE *KCC BEM 2-13-06 RBDms*
 810 Feet from North / South Section Line
 810 Feet from East / West Section Line
 Sec. 12 Twp. 3 S. R. 14 East West
 County: Nemaha
 Date Well Completed: 8-04-04
 Plugging Commenced: 1-10-06
 Plugging Completed: 1-12-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	268.3'	8 5/8	268.3'	None
	Production	GL	2754.85'	5 1/2	2754.85'	1034'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 1-10-06, ran tubing and tagged at 2587'. Spotted 2 bbls of gelled water (Had gel from 2587' to 2535'). Pulled tubing to 2535' and pumped 45 bbls of gelled water and spotted 35 sx of Class A cement plus 1 sx of cottonseed hulls. Displaced with 8.5 bbls of gelled water (Gel from 2250' to 300' and cement from 2250' to 2535'). On 1-12-06, shot casing at 1034' and pulled to 301'. Mixed and pumped 90 sx of Class A cement, circulated cement to surface and pulled casing.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006
 Address: PO Box 782228 Wichita KS 67278-2228

Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc.
 State of Kansas County, Sedgwick, ss.

Darrel G. Walters (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) PO Box 782228 Wichita KS 67278-2228

SUBSCRIBED and SWORN TO before me this 13th day of February, 2006
[Signature] My Commission Expires: 12-21-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2006
Mishkittell
CONSERVATION DIVISION
WICHITA, KS
My Comm Exp. 12-21-07

Bem