

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

FEB 16 2006

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Vincent Oil Corporation
Address: 125 N. Market, Suite 1075 Wichita, Kansas 67202
Phone: (316) 262-3573 Operator License #: 5004
Type of Well: oil and gas Docket #:
The plugging proposal was approved on: 12-26-05 (Date)
by: Durrant (KCC District Agent's Name)
Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No
Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4913 Bottom: 4927 T.D. 5051
Marmaton Depth to Top: 4771 Bottom: 4776 T.D.

API Number: 15 - 09721105 - 00 - 01
Lease Name: Greenleaf DWVO
Well Number: 1
Spot Location (QQQQ): - - SE - NE
3300 Feet from [] North / [X] South Section Line
660 Feet from [X] East / [] West Section Line
Sec. 2 Twp. 30 S. R. 18 [] East [X] West
County: Kiowa
Date Well Completed: 3-5-85
Plugging Commenced: 1-31-06
Plugging Completed: 2-2-06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows for Mississippian and Marmaton formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4900', dumped 4 sacks, ripped at 3050', pumped 20 bbls. of water to wash mud out of pipe, pulled to 1100' and pumped 12 sxs gel and 50 sxs of cement. Pulled to 360' and pumped 50 sxs, pulled to 40' and pumped 20 sxs.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 400 West Main, Lyons, KS. 67554


Name of Party Responsible for Plugging Fees: Vincent Oil Corporation
State of Kansas County, Sedgwick, ss.

Richard A. Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch
(Address) 125 N. Market, Suite 1075 Wichita, Kansas 67202

SUBSCRIBED and SWORN TO before me this 9th day of February, 2006

Yolanda Eubanks My Commission Expires:
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten signature/initials

ALLIED CEMENTING CO., INC. 22823

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <u>2-2-06</u>	SEC. <u>2</u>	TWP. <u>30S</u>	RANGE <u>18W</u>	CALLED OUT <u>8:00AM.</u>	ON LOCATION <u>11:30AM</u>	JOB START <u>12:00PM</u>	JOB FINISH <u>1:40PM</u>
LEASE <u>Greenleaf</u> WELL # <u>1</u>			LOCATION <u>54 & Center view Rd</u>		COUNTY <u>Kiowa</u>	STATE <u>Ks.</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<u>10S 1E 1/4S W/INTO</u>				

CONTRACTOR Quality W/S
 TYPE OF JOB O.H.P
 HOLE SIZE 7 7/8 T.D. 1100
 CASING SIZE 4 1/2 DEPTH 1100
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 200PSI MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____

OWNER Vincent Oil Co.
 CEMENT
 AMOUNT ORDERED 1205x 60:40:6
125x Gel

PERFS. _____
 DISPLACEMENT Fresh Water

COMMON	<u>72</u>	<u>A</u>	@	<u>8.70</u>	<u>626.40</u>
POZMIX	<u>48</u>		@	<u>4.70</u>	<u>225.60</u>
GEL	<u>18</u>		@	<u>14.00</u>	<u>252.00</u>
CHLORIDE			@		
ASC			@		
RECEIVED					
FEB 16 2006					
KCC WICHITA					
HANDLING	<u>138</u>		@	<u>1.60</u>	<u>220.80</u>
MILEAGE	<u>40</u>	<u>x 138</u>	<u>x .06</u>		<u>331.20</u>
					TOTAL <u>1656.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER David W.
 #372 HELPER Mike B.
 BULK TRUCK
 #389 DRIVER Jason K.
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

1st Plug at 1100 FT pump 125x Gel
Mix 505x cement Displace w/
9 BBIS, water 2nd Plug pump 0
360 BBIS, water Mix 505x cement
Displace 1 1/2 BBIS, water 3rd Plug
40 FT CMC Cement TO Surface
Wash up Rig Down.

CHARGE TO: Vincent Oil Co.
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	<u>1100</u>				
PUMP TRUCK CHARGE					<u>600.00</u>
EXTRA FOOTAGE			@		
MILEAGE	<u>40</u>		@	<u>5.00</u>	<u>200.00</u>
MANIFOLD			@		
					TOTAL <u>800.00</u>

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING TOTAL _____
 TAX _____
 TOTAL CHARGE ~~XXXXXXXXXX~~
 DISCOUNT ~~XXXXXXXXXX~~ IF PAID IN 30 DAYS

SIGNATURE X

J
 PRINTED NAME