

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED  
FEB 16 2006  
KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC  
Address: 125 N. Market, Wichita, KS 67202  
Phone: (620) 886-8606 Operator License #: 33168  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 1/25/2006 (Date)  
by: Eric Mac Cleren (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 3917 Bottom: 3929 T.D. 4200  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-225810000  
Lease Name: Oliver Bell  
Well Number: 1  
Spot Location (QQQQ): E2-W2-NE  
1320 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 29 Twp. 33 S. R. 13  East  West  
County: Barber  
Date Well Completed: 11/12/1998  
Plugging Commenced: 1/30/2006  
Plugging Completed: 2/1/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4	304	None
				5 1/2	4248	3200

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1/30 - Set CIBP at 3880', spot 2 sacks cement with dump bailer, 1/31 - stretch and cut pipe at 3200', pull casing, 2/1 - run 2 3/8" tubing to 650'  
Allied load hole with 10 sacks gel, pump 50 sacks 60/40 POZ 6%, pull tubing to 330', pump 75 sacks cement, pull to 40'  
load with 25 sacks

Name of Plugging Contractor: Clarke Corporation License #: 5105  
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC

State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford  
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 13 day of February, 20 06

Glenda Morrison My Commission Expires: 11/3/06  
Notary Public

*Sm*