

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

FEB 16 2006

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
Address: 100 S. Main, Suite 200, Wichita, KS 67202
Phone: (316) 262-3596 Operator License #: 9408
Type of Well: oil Docket #:
The plugging proposal was approved on: 2/2/06
by: Roger Moses
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Depth to Top: 3571' Bottom: 3577' T.D.
Depth to Top: 3162' Bottom: 3472' T.D.
Depth to Top: Bottom: T.D.

API Number: 15-051-00027-0001
Lease Name: Collins
Well Number: 1
Spot Location (QQQQ): - SW - SW - SW
330' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 12 Twp. 11 S. R. 19 East West
County: Ellis
Date Well Completed: 2/2/06
Plugging Commenced: 2/2/06
Plugging Completed: 2/2/06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Contains data for surface casing from 196' to 3689'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Express run 39 jts 2 3/8 tbg to 1189'. Allied Cement mixed 125 sxs 60/40 Poz Mix 10% gel + 350 # hulls. Tbg is stuck. Backed off tbg, left 12 jts in csg. Swedge csg and mix 30 sxs 60/40/ Pozmix 10% gel with 150# hulls. Shut in with 500 # on csg. Pump 75 sxs 60/40/pozmix 10% gel w/100# hulls down 8-5/8" csg. Press to 500 # Shut in. Roger Moses was the KCC witness.

Name of Plugging Contractor: Express Well Service License #: 6426
Address: P.O. Box 19, Victoria, KS 67671

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corp.


State of Kansas County, Sedgwick, ss.

Gary Sharp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Sharp
(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 14th day of February

Glenna E. Lowe My Commission Expires:
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Ben