

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Heartland Oil & Gas Corporation
Address: 1610 Industrial Park Drive Paola KS 66071
Phone: (913) 294-1400 Operator License #: 33233
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-28-05 (Date)
by: Taylor Herman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 2320 Bottom: 2474 T.D. 2722
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-131-20183-00-00
Lease Name: Georg
Well Number: 10-12
Spot Location (QQQQ): _____ - _____ - NW - SE
1880 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 12 Twp. 3 S. R. 14 East West
County: Nemaha
Date Well Completed: 8-07-04
Plugging Commenced: 1-16-06
Plugging Completed: 1-19-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	260'	8 5/8	260'	None
	Production	GL	2702'	5 1/2	2702'	1018'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

On 1-16-06, ran tubing and tagged at 2599'. Spotted 1.5 bbls of gelled water and pulled tubing to 2536'. Pumped 37 bbls of gelled water plus 10 bbls that was in tubing and spotted 30 sx of Class A cement plus 1 sx of cottonseed hulls. Displaced with 9 bbls of gelled water. Pulled tubing and had gel from 300' to 2270' with cement from 2270' to 2536'. On 1-19-06, shot casing at 1018' and pulled to 298'. Mixed and pumped 85 sx of Class A cement, circulated cement to surface and pulled casing.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006
Address: PO Box 782228 Wichita KS 67278-2228

Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc.
State of Kansas County, Sedgwick, ss. 2-21-06 BEM KCC
Darrel G. Walters

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 782228 Wichita KS 67278-2228

SUBSCRIBED and SWORN TO before me this 13th day of February, 2006
[Signature] My Commission Expires: 12-21-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2006
CONSERVATION DIVISION
WICHITA, KS
12-21-07
BEM