

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20008-00-00
Spot: NWSW Sec/Twnshp/Rge: 29-8S-25W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: KNOLL NORTH S Well #: 4
County: GRAHAM Total Vertical Depth: 4010 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3981	0	100 SXS CMT
SURF	8.625	215	0	170 SXS CMT

#130³³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2006 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 600# hulls.
TOF at 3199'.
Well squeezed at 1750'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2006 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3800' - mixed and pumped 100 sxs cement with 200# hulls.
Pulled up to 2400' - spotted 50 sxs cement with 100# hulls.
Pulled up to 1800' - circulated cement with 115 sxs cement with 100# hulls.
POOH. Swaged onto 5 1/2" and topped with 20 sxs cement with 50# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to the annulus and pumped 100 sxs cement with 100# hulls.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3921	3930		
3906	3908		
3881	3886		
3828	3834		
3793	3796		
3781	3785		

Remarks: LEASE ORIGINALLY KNOWN AS STEPHENSON #4. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 2-22-06

NO. 2006061166

RECEIVED

FEB 22 2006

KCC WICHITA

Form CP-2/3

FEB 20 2006

1
aka Knoll North S-4

ROCK ISLAND OIL & REG CO #4 STEPHENSON 29-8-25W
 C NW SW
 Contr. RED TIGER DR LG City GRAHAM
 Geol. Pool KNOLL NORTH
 E. 2487 KB. Cm. 1/25/67. Cp. 3/2/67 IPPMP. 216 BOPD, NW
 LANS 3881-3930

LOG Tops	Depth	Datum	Csg.
			API 15-065-20,008 8" 215/170 sx; 5" 3981/100 sx;
CIM ANHY	2184	+303	DST 3769-3810/1', 1660' GIP, 2150' OIL, BHP 1322-1318#/30", FP 624-808#;
LANS	3751	-1264	DST 3809-42, MISRUN;
B/KC	3976	-1489	DST 3809-42/1', 270' GIP, 210' v GSY OCM; BHP 1241-1236#; FP 122-90#;
			PF 24/3881-86; 8/3906-08; 36/3921- 30, A 3000, SWB 86 BOPH, NW, NT, POP.
LTD	4009	-1522	
RTD	4010	-1523	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

INDEX