

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23135-00-00  
Spot: SWNENWNW Sec/Twnshp/Rge: 27-7S-22W  
560 feet from N Section Line, 910 feet from W Section Line  
Lease Name: STEVENSON-LUCKY Well #: 3  
County: GRAHAM Total Vertical Depth: 3681 feet

Operator License No.: 30259  
Op Name: WERTH, ANDY DBA WERTH EXPLORA  
Address: 1308 SCHWALLER AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	200		

#119<sup>63</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2006 9:00 AM  
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING  
Proposal Rcvd. from: DARRELL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES WitnessType: NONE  
Date/Time Plugging Completed: 02/12/2006 10:45 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

1st. Plug at 1850' w/25 sxs.  
2nd. Plug at 1090' w/100 sxs.  
3rd. Plug at 260' w/40 sxs.  
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.  
Rathole with 15 sxs.  
Total of 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

INVOICED

DATE 2-22-06

INV. NO. 2006061170

RECEIVED

FEB 22 2006

KCC WICHITA

Form CP-2/3

FEB 20 2006