

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00027-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 12-11S-19W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: COLLINS OWWO Well #: 1
County: ELLIS Total Vertical Depth: 3690 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3689	0	200 SX CMT
SURF	8.625	225	0	175 SX CMT

#119 93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2006 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 250 sxs cement and 600# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2006 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Junk in the hole at 1189'.
Ran tubing to 1180' - circulated with 125 sxs cement with 350# hulls.
Tubing stuck - backed off 28 joints and left 13 joints in the hole.
Tied to 5 1/2" casing - squeezed with 30 sxs cement with 150# hulls.
Max. P.S.I. 800#. S.I.P. 500#.
Tied to 8 5/8" x 5 1/2" - squeezed 75 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 500#.
Total fo 230 sxs 60/40 pozmix - 10% gel and 600# hulls.

Perfs:

Top	Bot	Thru	Comments
3571	3577		
3162	3472		

Remarks: LEASE ORIGINALLY KNOWN AS THE MOLLILAR #1. ALLIED CEMENTING COMPANY. BLACKHAWK TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger A Moses

(TECHNICIAN)
RECEIVED

FEB 22 2006

KCC WICHITA

INVOICED

DATE

2-22-06

INV. NO

2006061169


FEB 20 2006

ROBERT R. PRICE OPERATING, INC. #1 COLLINS 'OWWO' 12-11-19W
 P.O. BOX 45442 TULSA, OK 74145 SW SW SW

CONTR RANGER DRILLING CO., INC. CTY ELLIS

GEOL _____ FIELD SOLOMON NE EXT & CONF (1/8 N)

ELV 2001 KB SPD 9/14/82 CARD ISSUED 1/27/83 IP P 3.5 BO & 88 BWPD
1995 GL SHAW 3162-3251 OA
 API NOT ASSIGNED LKC 3252-3472 CA



SMP	Tops	Depth-Datum
ANH	1345	656
TOP	2989	988
HEEB	3212	1211
LANS	3252	1251
BKC	3480	1479
CONG	3509	1508
SIMP	3528	1527
ARB	3569	1568
OTD	3590	1589
LTD	3649	1648
DDTD	3690	1689

(NEW PAY - SHAW OIL)

OLD INFO: OPERATOR WAS WALTERS DRILLING CO. #1 MOLLI-LAR, SPD NA, SET 8" 225; COMPLETED AS D&A / ARB 6/20/52, CONTR: UNKNOWN
 DST (1) 3409-51 (LKC) / OP 45", REC 25'M, PRESS NA
 DST (2) 3500-21 (PENN, CONG) : OP 50', REC 4'M, PRESS NA
 DST (3) 3538-78 (SIMP, ARB) / OP 1 HR, REC 40' OCM, SIP 750#
 DST (4) 3578-90 (ARB) / OP 30", REC 30' MO, SIP 1000
 NEW INFO: RE-ENTERED ON 9/14/82. WSH DWN TO OTD, DDTD 3690, SET 5 1/2" 3689/200SX, MICT - CO, PF (ARB) 3571-77, W / 1 SPF, AC 600G, SWB LD, NSO, SET CIBP AT 3542, PF (SHAW) 3162-3251 OA, PF (LKC) 3252-3472 OA, W / 1 SPF, AC 13,500G (15% HCL), SWB LD & SSO, FRAC W / 500,000 SCFN2, 1000# GEL SALT PLUG & 120 BBLS FOAM, SWB PT FRAC, GSO, POP, P 3.5 BO & 88 BWPD (GR 27°), 12/1/82, COMMINGLED

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

12-11-19W
 8749
 1MADICEN