

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23663-00-00
Spot: NENESE Sec/Twnshp/Rge: 13-11S-19W
2320 feet from S Section Line, 330 feet from E Section Line
Lease Name: METZ A Well #: 1
County: ELLIS Total Vertical Depth: 3550 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3549	0	225 SX CMT
SURF	8.625	203	0	150 SX CMT

#115³⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2006 11:15 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 250 sxs cement and 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2006 3:40 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfed at 1340' and circulated with 300 sxs cement.
Tied to 5 1/2" casing - squeezed 215 sxs cement with 600# hulls.
Max. P.S.I. 800#. S.I.P. 500#.
Tied to 8 5/8" and pressured to 1000# - took no cement.
Total of 215 sxs 60/40 pozmix - 10% gel and 600# hulls.

Perfs:

Top	Bot	Thru	Comments
3407	3446		
3149	3398		
2908	3130		

Remarks: BLACKHAWK TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger J. Moses
(TECHNICIAN)

INVOICED
DATE 2.22.06
INV. NO. 2006061169

RECEIVED
FEB 22 2006
KCC WICHITA

FEB 20 2006

ROBERT R. PRICE OPERATING, INC.

P. O. BOX 470442
TULSA, OK 74147

#1 "A" METZ

13-11-19W
10'N,

C NE NE SE


CONTR. RANGER DRILLING CO., INC.

CTY ELLIS

GEOLOGICAL

FIELD

COCHRAN WEST EXT
(1/8 s)



ELV 1922 KB SPD 12/1/83 CARD ISSUED 5/10/84

IP P 7 BO & 80 BWP

1917 GL
API 15-051-23,663

SHAW 2936-?

LKC 3172-3408 OA

MARM 3409-3444 OA

LOG	Tops	Depth/Datum
ANH	1270 + 652
TOP	2908- 986
HEEB	3130-1208
TOR	3150-1228
LANS	3172-1250
BKC	3400-1478
MARM	3409-1487
SIMP DOL	3469-1547
ARB	3489-1567
LTD	3531-1609
RTD	3550-1628

8 5/8 " 203 / 150SX; 5 1/2 " 3549 / 225SX

NO DSTS
MICT - CO, PF (ARB) 3490-94, W / 1 SPF, SWB DWN, NON-
COMMERCIAL, SET CIBP AT 3475, PF (SHAW) 2936-7, W / 1 SPF,
PF (LKC) 3172-3408 OA (EST), W / 1 SPF, PF (MARM) 3409-44
OA (EST), W / 1 SPF, AC 14,000G (28% HCL) OA PFS, SWB DWN,
SO, PF (ANH) 4 / 1265, SQZ'D W/300SX, POP, P 7 BO & 80
BWP (GR 29"), 3/13/84, COMMINGLED - NO OTHER INFO RE-
LEASED BY OPERATOR CONCERNING SELECTED PF INTV'S

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

WAC:GEM