

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21536-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 22-13S-20W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: HERMAN Well #: 2  
County: ELLIS Total Vertical Depth: 3863 feet

Operator License No.: 6127  
Op Name: KORON, JEFF DBA TAURUS OIL COMP  
Address: PO BOX 981  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3852	0	w/100 sxs cmt
SURF	8.625	167	0	w/135 sxs cmt

#125<sup>SS</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/01/2006 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JEFF KORON Company: TAURUS OIL COMPANY Phone: (785) 628-1727

Proposed Plugging Method: Ordered 200 sxs cement - 20 sxs gel and 500# hulls.

Plugging Proposal Received By: ROGER MOSES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/01/2006 4:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Squeezed at 1025' w/290 sxs cement.  
Squeezed at 1274' w/200 sxs cement.  
Squeezed at 2450' w/250 sxs cement.  
Tied to 5 1/2" casing - spotted 35 sxs cement with 100# hulls, followed with 18 sxs gel.  
Squeezed casing with 175 sxs cement and 400# hulls.  
Max. P.S.I. 1000#. S.I.P. 850#.  
Pressured 8 5/8" to 500# P.S.I.  
Total of 210 sxs 60/40 pozmix - 10% gel - 18 sxs gel and 500# hulls.

Perfs:

Remarks: BLACKHAWK TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger D. Moses  
(TECHNICIAN)

100 -  
**INVOICED**

DATE

2-22-06

TV. NO

2006061168

RECEIVED

FEB 22 2006

KCC WICHITA


Form CP-2/3

FEB 20 2006

JOHN B. COLLINS  
 1007 CODY, SUITE A #2 HERMAN 22-13-20W  
 HAYS, KS. 67601 NW SW SW  
 CONTR DREILING OIL, INC. CTY ELLIS

GEOL \_\_\_\_\_ FIELD PLEASANT

E 2233 KB CM 8/8/78 CARD ISSUED 10/5/78 IP P 18 BOPD N/W  
 ARB 3852-63



API 15-051-21,536

SMP	TOPS	DEPTH	DATUM
ANH		1551	- 682
TOP		3220	- 987
HEEB		3468	-1235
TOR		3486	-1253
LANS		3507	-1274
B KC		3762	-1529
MARM		3813	-1580
ARB		3851	-1618
RTD		3863	-1630

8-5/8" 167/135 SX, 5 1/2" 3852/100 SX  
 DST (1) 3569-3630/30-45, 360' MW, FSIP  
 981#, FP 78-151#  
 DST (2) 3830-60/30-45-10, 65' OCM, SIP  
 981#, FP 65-98#  
 MICT - CO & DRILL PLUG, FU 1000 OIL,  
 NAT, AC 500, REC LD, SWB 3 1/2 BOPH/4  
 HRS, POP  
 NO LOG

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

WICHITA