

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23731-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 29-14S-19W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WILSON B Well #: 3
County: ELLIS Total Vertical Depth: 3830 feet

Operator License No.: 6127
Op Name: KORON, JEFF DBA TAURUS OIL COMP
Address: PO BOX 981
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3829	0	625 SX CMT W/DV TOOL.
SURF	8.625	258	0	150 SX CMT
UNK		0		

#12448

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2006 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JEFF KORON Company: TAURUS OIL COMPANY Phone: (785) 628-1727

Proposed Plugging Method: Ordered 200 sxs cement - 20 sxs gel - 500# hulls.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2006 1:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Tied to 5 1/2" casing - spotted 35 sxs cement with 100# hulls - spotted 20 sxs gel.
Squeezed 120 sxs cement with 400# hulls.
Max. P.S.I. 1000#. S.I.P. 650#.
Tied to 8 5/8" - pressured to 500# P.S.I. - no cement.
Total of 155 sxs 60/40 pozmix - 10% gel - 20 sxs gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3776	3829		

Remarks: BLACKHAWK TANK-WATER

Plugged through: CSG

District: 04

Signed Roger L Moses

(TECHNICIAN)

INVOICED

DATE 2-22-06

INV. NO. 2006061168

RECEIVED

FEB 22 2006

KCC WICHITA

Form CP-2/3

FEB 13 2006

TAM OIL & GAS COMPANY
2700 OAK ST., SUITE A


#3 "B" WILSON

29-14-19W
NW NW NE

HAYS, KS 67601

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOLOGICAL CLIFF OTTAWAY FIELD KRAUS



ELV 2152 KB SPD 12/23/83 CARD ISSUED 3/22/84 IP P 12 BO & 500 BWPD
2147 GL ARB 3776-3782

LOG	Tops	Depth/Datum
ANH	1414 + 738
TOP	3138- 986
HEEB	3401-1249
TOR	3423-1271
LANS	3448-1296
BKC	3695-1543
MARM	3736-1584
GOR SD	3758-1606
ARB	3776-1624
LTD&RTD	3830-1678

API 15-051-23,731

8 5/8 " 258 / 150SX; 5 1/2 " 3829 / 625SX

DST (1) 3570-3645 (LKC) / 30-30-30-30, REC 60' OIL SPKD M,
SIP 143-143#, FP 50-58 / 67-74#

DST (2) 3740-72 (MARM, GOR SD) / 30-30-30-30, REC 62' MW,
W / SSO, SIP 597-412#, FP 42-50 / 50-58#

DST (3) 3742-83 (MARM, GOR SD, ARB) / 60-30-60-30, REC
240' CL OIL, 630' FROGGY OIL, SIP 1092-1083#, FP 67-227 /
244-345#

MICT - CO, PF (ARB) 3776-82, W / 4 SPF, AC 400G (15%), SWB
LD & REC 50 BFPH (EST 10% OIL), 800' OFF BTM, POP, P 40 BO
& 260 BWPD, 1/27/84, DECL & STAB AT 12 BO & 500 BWPD, 3/9/
84

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

INDEXED