

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23625-00-00
Spot: NENWNE Sec/Twnshp/Rge: 29-14S-19W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WILSON B Well #: 1
County: ELLIS Total Vertical Depth: 3790 feet

Operator License No.: 6127
Op Name: KORON, JEFF DBA TAURUS OIL COMP
Address: PO BOX 981
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3786	0	175 SX CMT W/ DV TOOL
SURF	8.625	248	0	175 SX CMT

#123

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2006 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JEFF KORON Company: TAURUS OIL COMPANY Phone: (785) 628-1727

Proposed Plugging Method: Ordered 200 sxs cement - 20 sxs gel - 500# hulls.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2006 12:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV Tool at 1460' w/400 sxs cement.
Tied to 5 1/2" casing - spotted 35 sxs cement - 10% gel and 165 sxs cement with 500# hulls.
Max. P.S.I. 400#. S.I.P. 300#.
Tied to 8 5/8" x 5 1/2" - pressured to 500# P.S.I. - took no cement.
Total of 190 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3766	3789		

Remarks: BLACKHAWK TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

INVOICE

DATE 2-22-06
NO. 2006061168

RECEIVED

FEB 22 2006

KCC WICHITA


Form CP-2/3

FEB 13 2006

TAM OIL AND GAS COMPANY
 2700 OAK STREET, SUITE A #1 "B" WILSON 29-14-19W
 HAYS, KS 67601 NE NW NE

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOLOGICAL CLIFF OTTAWAY FIELD KRAUS



ELV 2169 KB SPD 10/3/83 CARD ISSUED 1/19/84 IP P 7 BO & 67 BWPD
 2164 GL ARB 3765-3775
 API 15-051-23,625

LOG	Tops	Depth/Datum	
			8 5/8 " 248; 5 1/2 " 3786/175 SX
			DST (1) 3580-3660 (LKC) / 60-30-60-30, REC 185' GSY MCO, SIP 451-609#, FP 66-117#
ANH	1431+	738	DST (2) 3750-90 (ARB) / 60-30-30-30, 375' GSY FREE OIL. 360'
B/ANH	1472+	697	HOCM, SIP 892-867#, FP 91-251#
TOP	3147-	978	MICT - CO. PF (ARB) 3765-75, W/2 SPF, AC 400 G (15%), SWB
HEEB	3414-	1245	LD, SO, POP, P 7 BO & 67 BWPD, 10/27/83
TOR	3436-	1267	
LANS	3462-	1293	
BKC	3705-	1536	
MARM	3743-	1574	
ARB	3766-	1597	
RTD	3790-	1621	

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

15A01CEN
 0748
 15A01CEN