

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24895-00-00  
Spot: S2SWNE Sec/Twnshp/Rge: 11-16S-11W  
2200 feet from N Section Line, 2000 feet from E Section Line  
Lease Name: HOUSKA Well #: 3-11  
County: BARTON Total Vertical Depth: 3390 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1670 BROADWAY #3300  
DENVER, CO 80202

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF   | 8.625 | 430        |             |         |

#110<sup>18</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2006 9:00 PM  
Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC  
Proposal Rcvd. from: ROBIN ROACH Company: SAMUEL GARY JR. & ASSOCIATES Phone: (202) 831-4673

Proposed Plugging Method: Order 150 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 02/17/2006 3:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3302' w/35 sxs.  
2nd. Plug at 1350' w/25 sxs.  
3rd. Plug at 620' w/25 sxs.  
4th. Plug at 475' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

FEB 20 2006

INVOICED  
DATE 2-22-06  
INV. NO. 2006061167

RECEIVED  
FEB 22 2006  
KCC WICHITA