

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23142-00-00
Spot: SENW Sec/Twnshp/Rge: 34-9S-21W
1860 feet from N Section Line, 2110 feet from W Section Line
Lease Name: DEYOUNG Well #: 1-34
County: GRAHAM Total Vertical Depth: 3975 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

#129¹⁹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/17/2006 4:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 02/17/2006 6:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3850' w/25 sxs.
2nd. Plug at 1815' w/25 sxs.
3rd. Plug at 1050' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 2-22-06

NO. 2006061164

RECEIVED

FEB 22 2006

KCC WICHITA

Form CP-2/3

FEB 20 2006