

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25489-00-00
Spot: NWNESE Sec/Twnshp/Rge: 24-11S-18W
2410 feet from S Section Line, 990 feet from E Section Line
Lease Name: MARSHALL E Well #: 26
County: ELLIS Total Vertical Depth: 1565 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	252		

50⁸⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/10/2006 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TOM BARNES Company: LARIO OIL & GAS COMPANY Phone: (785) 625-5023

Proposed Plugging Method: Ordered out 150 sxs Swift Multi-Density Cement and 30 sxs common.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/10/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

TIH with tubing to 1112' - spotted 30 sxs common with 2% cc.
Let set up two hours - RIH and tagged TOC at 970'.
Pulled up to 810' - spotted 50 sxs SMD.
Pulled up to 290' - circulated cement with 45 sxs SMD.
Pulled out of the hole and topped with 10 sxs SMD.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
FEB 15 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 2-15-06
WT. NO 2006061118

Form CP-2/3

FEB 13 2006