

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20612-00-00  
Spot: E2NENWNE Sec/Twnshp/Rge: 34-16S-32W  
330 feet from N Section Line, 1460 feet from E Section Line  
Lease Name: CAUTION TRUST Well #: 1-34  
County: SCOTT Total Vertical Depth: 4710 feet

Operator License No.: 31652  
Op Name: NORSTAR PETROLEUM, INC.  
Address: 6855 S. HAVANA ST., STE 250  
CENTENNIAL, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	250		WITH 175 SX CMT

#153<sup>08</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/08/2006 4:15 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Revd. from: GREG Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 40 SX CMT. 4TH PLUG AT 260' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 02/08/2006 7:15 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_


1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 40 SX CMT. 4TH PLUG AT 260' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED  
FEB 16 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed Michael Maier  
(TECHNICIAN)

INVOICED  
DATE 2-16-06  
INV. NO. 20060611/33

Form CP-2