

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23798-00-00
Spot: W2SWNW Sec/Twnshp/Rge: 29-16S-22W
1980 feet from N Section Line, 330 feet from W Section Line
Lease Name: MUSSELMAN Well #: 1
County: NESS Total Vertical Depth: 4493 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4493	0	WITH 100 SX CMT
SURF	8.625	217		WITH 140 SX CMT

#146⁰²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2006 9:20 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: PUMP 35 SX CMT & 2003 HULLS ON BOTTOM. GEL TO ANHYDRITE THEN CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2006 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CMT FROM 1758' TO SURFACE WITH 300 SX CMT. PUMP 35 SX CMT & 200# HULLS. PUMP 20 SX GEL MIXED WITH 60 BBL WATER TO ANHYDRITE THEN 145 SX CMT. MAXIMUM PRESSURE 1800#. SHUT IN PRESSURE 1600#. TIE ONTO BACKSIDE AND PUMP 35 SX CMT. PRESSURED TO 500#.

Perfs:


Top	Bot	Thru	Comments
4422	4434		

RECEIVED
FEB 16 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 0



Signed

Michael J Maier
(TECHNICIAN)

INVOICED

DATE 2-16-06

BY 20060611 31

Form CP-2