

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22048-00-00
Spot: N2NESE Sec/Twnshp/Rge: 10-34S-35W
2610 feet from S Section Line, 660 feet from E Section Line
Lease Name: SKINNER B Well #: 3
County: STEVENS Total Vertical Depth: 2885 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2650		WITH 2 SX CMT
PROD	5.5	2882	520	WITH 400 SX CMT #9376
SURF	8.625	821		WITH 280 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/23/2006 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2650' WITH 2 SX CMT. PLUG AT 1680' WITH 25 SX CMT. PLUG AT 850' WITH 25 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2006 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 2650' WITH 2 SX CMT. 1ST PLUG MUD SPACER TO 1680' & PUMP 25 SX CMT INSIDE 5 1/2". 2ND PLUG PUMP MUD SPACER TO 850' & PUMP 25 SX CMT INSIDE 5 1/2" CASING. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2758	2761		
2704	2710		
2686	2690		
2676	2680		


RECEIVED
FEB 15 2006

Remarks: USED COMMON CEMENT BY SARGENTS.

KCC WICHITA

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 2-15-06
INV. NO 2006061123

Form CP-2/3