

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-033-20992-00-00
 Spot: N2N2N2 Sec/Twnshp/Rge: 22-31S-18W
330 feet from N Section Line, 2690 feet from E Section Line
 Lease Name: BOISSEAU Well #: 1-22
 County: COMANCHE Total Vertical Depth: 5851 feet

Operator License No.: 33168
 Op Name: WOOLSEY OPERATING COMPANY, LL
 Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4950		WITH 3 SX CMT
CIBP		5142		
PROD	4.5	5505	2500	WITH 200 SX CMT
SURF	10.75	340		WITH 275 SX CMT

#190¹⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2006 9:00 AM
 Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
 Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4950' & PLACE 3 SX CMT ON TOP W/DUMP BAILER. SPOT 10 SX GEL & 75 SX @ 1000', 75 SX @ 360' & CIRCULATE FROM 40' TO SURFACE. W/15 SX. USE 60/40 POZ + 6% GEL.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 02/10/2006 10:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 4950' WITH 3 SX CMT. 1ST PLUG AT 1000' WITH 10 SX GEL - 75 SX CMT. 2ND PLUG AT 360' WITH 75 SX CMT. 3RD PLUG AT 40-0' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5146	5152		
5124	5132		
5015	5023		
4972	4982		

RECEIVED
 FEB 16 2006
 KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.
 Plugged through: CSG

District: 01

RECEIVED
 FEB 13 2006
 KCC Dodge City

Signed Eric MacLaren
 (TECHNICIAN)

INVOICED
 DATE 2-16-06
 INV. NO. 2006061136

Form CP-228