

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20749-00-00
Spot: NENESWNW Sec/Twnshp/Rge: 36-30S-38W
3876 feet from S Section Line, 4032 feet from E Section Line
Lease Name: JARVIS Well #: 4-36
County: GRANT Total Vertical Depth: 3000 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA,
Address: 5205 N. O'CONNOR BLVD.,
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2410		WITH 2 SX CMT
PROD	5.5	2999	0	WITH 400 SX CMT
SURF	8.625	713		WITH 300 SX CMT

\$ 97⁵⁰

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2006 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2410' WITH 2 SX CMT. PLUG AT 1750' WITH 20 SX CMT. PLUG AT 750' WITH 20 SX CMT. 10 SX CMT TO SURFACE. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2006 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 2410' WITH 2 SX CMT. 1ST PLUG AT 1750' WITH 20 SX CMT. 2ND PLUG AT 750' WITH 20 SX CMT. 3RD PLUG AT 100'-0 WITH 10 SX CMT. PRESSURE TO 500# & SHUT IN. PUMP 19 SX CMT DOWN BACKSIDE. PRESSURE TO 500# & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
2460	2778		

INVOICED


Remarks: USED COMMON CEMENT BY SARGENTS.

DATE 2-21-06

Plugged through: CSG

TEL. NO. 2006061155

District: 01



Signed

Jim Holland **DIRT II**
RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

FEB 21 2006

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3