

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20463-00-00  
Spot: S2S2NW Sec/Twnshp/Rge: 22-10S-25W  
2970 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: BRUNGARDT B Well #: 2  
County: GRAHAM Total Vertical Depth: 4260 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: P.O. BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4256	0	200 SX CMT
SURF	8.625	201	0	160 SX CMT

#138<sup>45</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2006 2:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: MARK LEIKER Company: BEREN CORPORATION Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Well squeezed at 3000'-3125' w/227 sxs; 1477'-1509' w/500 sxs; 1800' w/150 sxs; 2064'-2123' w/90 sxs.  
TOF at 3700'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/15/2006 5:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3600' - mixed and pumped 50 sxs.  
Pulled up to 3000' - spotted 50 sxs cement with 100# hulls.  
Pulled to 2400' - spotted 50 sxs cement with 100# hulls.  
Pulled to 1800' - spotted 50 sxs cement with 100# hulls.  
Pulled up to 1200' - circulated cement up 5 1/2" with 50 sxs cement with 100# hulls.  
POOH. Swaged onto 5 1/2" - pumped 30 sxs cement with 100# hulls.  
S.I.P. 400#.  
Hooked up to the 8 5/8" and pumped 100 sxs cement with 200# hulls.  
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3943	3950		
3888	3892		
3844	3851		
3789	3798		

RECEIVED  
FEB 21 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed: Jay Pfeifer  
(TECHNICIAN)

INVOICED

DATE 2.21.06  
WEL NO 200606156

Form CP-2/3

FEB 16 2006

