

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20515-00-01
Spot: SENW Sec/Twnshp/Rge: 2-31S-18W
3298 feet from S Section Line, 3241 feet from E Section Line
Lease Name: UNRUH D Well #: 1
County: COMANCHE Total Vertical Depth: 5121 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	277		WITH 250 SX CMT
PROD	5.5	5120	3620	WITH 175 SX CMT
SURF	8.625	987		WITH 450 SX CMT

\$ 166.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2005 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK WITH 5 SX CMT OR CIBP @ 4800' WITH 2 SX CMT. PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2005 4:30 PM KCC Agent: GREG PATTERSON

Actual Plugging Report:

SAND BACK TO 4815 THEN 5 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. GOOD CIRCULATION.

Perfs:


Top	Bot	Thru	Comments
5042	5047		
5034	5037		
4939	4941		
4916	4924		
4865	4872		

INVOICED
DATE 2-21-06
INV. NO. 2006061153

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Greg Patterson
(TECHNICIAN) *GP*

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 21 2006

CONSERVATION DIVISION
WICHITA, KS