

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19105-00-00
Spot: N2S2SWSW Sec/Twnshp/Rge: 25-21S-4E
535 feet from S Section Line, 4681 feet from E Section Line
Lease Name: DAVIS SWD Well #: 6
County: MARION Total Vertical Depth: 3174 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2600	0	450 SX CMT
SURF	8.625	165	0	120 SX CMT

#103¹⁶

Well Type: SWD UIC Docket No: D06451.0 Date/Time to Plug: 09/23/2005 10:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BENNY KEY Company: SHAWMAR OIL & GAS CO., INC. Phone: (620) 382-2932

Proposed Plugging Method: OH 2600' to 3134'. Sand to 2550' & 5 sxs cement. 5-1/2" cemented from 2600' to 0'. Circ cement from 250' to 0'. Check 8-5/8" x 5-1/2" annulus for cement.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 09/23/2005 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2550' and capped with 5 sacks of cement. Perforated 5-1/2" casing at 250'. Ran tubing to 273' and circulated 35 sacks of cement to surface. Ran 1" tubing to 26' and filled 8-5/8" x 5-1/2" casing with 2 sacks of cement.

Class A cement

Consolidated #5390

Perfs:

Top	Bot	Thru	Comments
2600			

RECEIVED
KCC DISTRICT #2
FEB - 17 2006
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

RECEIVED
FEB 17 2006
KCC WICHITA

INVOICED
DATE 2-17-06
INV. NO. 2006061144