

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21177-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 30-14S-9W
2310 feet from S Section Line, 2250 feet from E Section Line
Lease Name: LANGE A Well #: 1-30
County: ELLSWORTH Total Vertical Depth: 3236 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	340		250 SX CMT

#105¹⁷

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/17/2006 2:30 PM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 35 sxs @ top of Arb; 35 sxs @ 1250'; 35 sxs @ 800'; 35 sxs @ 390'; 25 sxs @ 60'; 15 sxs in rathole; and 10 sxs in mousehole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/17/2006 7:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Filled hole with heavy mud and spotted cement through the drill pipe. Spotted 35 sacks of cement at 3185'; spotted 35 sacks of cement at 1250'; spotted 35 sacks of cement at 800'; spotted 35 sacks of cement at 390'; and spotted 25 sacks of cement at 60'. Filled rathole with 15 sacks of cement and filled mousehole with 10 sacks of cement.

60/40 posmix with 4% gel

Allied

RECEIVED
KCC DISTRICT #2
FEB - 3 2006
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed

Michael Wilson

(TECHNICIAN)

RECEIVED
FEB 17 2006
KCC WICHITA

INVOICED

DATE

2-17-06

INV. NO

2006061145