

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-19011-00-01  
Spot: SENESE Sec/Twnshp/Rge: 15-29S-7W  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease Name: VORAN Well #: 2  
County: KINGMAN Total Vertical Depth: 4481 feet

Operator License No.: 5387  
Op Name: BUCKEYE CORP., AZTEC OIL CO. DIVI  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3850		
PROD	5.5	4474		225 SX CMT
SURF	8.625	265		200 SX CMT

*63*  
*\$145*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2006 9:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE KILE Company: AZTEC OIL COMPANY Phone: (316) 321-6690

Proposed Plugging Method: Perfs 3758' - 3763' & 3724' - 3730'; CIBP @ 3850'; tubing anchor @ 3661'; casing leak @ 667' - 789'; set CIBP 50' above perfs; 35 sxs @ 1050'; 35 sxs @ 700'; and circ cement from 300' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/31/2006 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 3655' above the perforations. The casing was perforated at 1050'. Tubing and packer was ran to 1045' where 25 sacks of cement was pumped. The tubing was pulled to 825'. The packer was set and 2 bbls of water was pumped to displace the cement out of the casing. Waited 2-1/2 hours; didn't find any fill-up. Ran in hole with tubing and spotted 50 sacks of cement with 100 lbs of cotton hulls. Went on vacuum and waited 1-1/2 hours; no tag to 1080'. Ran in hole to 980' and spotted 75 sacks of cement with 100 lbs of cotton hulls. Shut down for the night. Tagged cement at 622' next morning. Pulled 324' casing and circulated 168 sacks of cement.

60/40 posmix with 4% gel & 2% CaCl

Perfs:

Top	Bot	Thru	Comments
3758	3763		
3724	3730		

RECEIVED  
KCC DISTRICT #2  
FEB 14 2006  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*[Handwritten Signature]*  
(TECHNICIAN)

RECEIVED  
FEB 17 2006  
KCC WICHITA

INVOICED

DATE 2-17-06  
INV. NO 2006061142