


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-179-00176-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

SHERIDAN County. Sec. 1 Twp. 7S Rge. 26 (E) (W) EST  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner R. W. SHIELDS AND CONTINENTAL OIL COMPANY  
Lease Name HESKETT Well No. 1  
Office Address 400 BROWN BLDG., WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed AUGUST 28 1956  
Application for plugging filed AUGUST 28 - VERBAL 1956  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced AUGUST 28 1956  
Plugging completed AUGUST 28 1956  
Reason for abandonment of well or producing formation \_\_\_\_\_  
DRY HOLE

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4280 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	323'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

BOTTOM PLUG SET AT 315' WITH 15 SACKS CEMENT.  
TOP PLUG SET @ 40' WITH 1/2 SACK HULLS AND 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 400 BROWN BLDG., WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, DAN J. KORNFELD,

(operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
DAN J. KORNFELD  
400 BROWN BLDG., WICHITA 2, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 10TH day of AUGUST, 1956

My Commission Expires June 7, 1960

[Signature]  
Notary Public.

My commission expires \_\_\_\_\_

PLUGGING  
FILE SEC 1 T 7 R 26W  
BOOK PAGE 95 LINE 4

10-23-56

15-179-00176-00-00

LOG

COMPANY: R.W. SHIELDS AND CONTINENTAL OIL COMPANY

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: HESKETT No. 1

LOCATION: SE SE SW OF SEC. 1-7S-26W, SHERIDAN COUNTY, KANSAS

COMMENCED: AUGUST 16, 1956

COMPLETED: AUGUST 28, 1956

ELEVATION: 2560' K.B.

-----					
0	TO	223	CLAY AND SAND	<u>TOPS:</u>	
223	TO	343	SAND AND SHALE		
343	TO	1950	SHALE AND SAND	ANHYDRITE	2165 + 395
1950	TO	2165	SHALE AND SHELLS	HEEBNER	3642 -1082
2165	TO	2200	ANHYDRITE	LANSING KANSAS CITY	3680 -1120
2200	TO	2722	SHALE AND SHELLS	BASE KANSAS CITY	3883 -1323
2722	TO	3185	SHALE AND LIME	MISSISSIPPI	4149 -1589
3185	TO	3355	LIME AND SHALE	VIOLIO	4176 -1616
3355	TO	3470	SHALE AND SHELLS	ARBUCKLE	4226 -1666
3470	TO	3580	SHALE AND LIME		
3580	TO	3620	LIME AND SHALE		
3620	TO	3925	LIME		
3925	TO	4067	SHALE AND LIME		
4067	TO	4150	SHALE		
4150	TO	4224	SHALE AND LIME		
4224	TO	4280	ARBUCKLE		
4280			R.T.D.		

DRY AND ABANDONED

CASING: RAN 323' OF 8 5/8" AND CEMENTED WITH 175 SACKS CEMENT.

D.S.T. #1 3698-3715 OPEN 1 HR. WEAK BLOW FOR 1 HR. RECOVERED 135' MUDDY SALT WATER. BHP 1150# IN 20 MINUTES.

D.S.T. #2 3720-3742 OPEN 1/2 HR. WEAK BLOW FOR 3 MIN. RECOVERED 15' VERY SLIGHTLY OIL CUT MUD. BHP 1115# IN 20 MINUTES.

CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE HESKETT No. 1 SE SE SW OF SEC. 1-7S-26W, SHERIDAN COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

*Dan J. Kornfeld*  
\_\_\_\_\_  
DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 10TH DAY OF SEPTEMBER, 1956.

*Charlotte Stanley*  
\_\_\_\_\_  
NOTARY PUBLIC

MY COMMISSION EXPIRES My Commission Expires June 7, 1960

STATE OF KANSAS

10-23-56

PLUGGING  
FILE SEC. 1 T. 7 R. 26W  
BOOK PAGE 95 LINE 4

CONTINENTAL OIL COMPANY