

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Sheridan County. Sec. 2 Twp. 7 Rge. 26 (E) (W)

Location as "NE/CNW¹/₄SW¹/₄" or footage from lines NW NW NW

Lease Owner Anschutz Drilling Company, Inc.

Lease Name Andregg Well No. 1

Office Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-8 19 52

Application for plugging filed 6-8 19 52

Application for plugging approved 6-8 19 52

Plugging commenced 6-8 19 52

Plugging completed 6-8 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Eldon Petty

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4472 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	227'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 40' with 10 sacks cement
Bottom plug set at 215' with 15 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

6-17-52

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Company, Inc.
Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler
709 Union Nat'l Bk Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of June, 1952

My commission expires May 2, 1956
Jacqueline Hanna Notary Public.

PLUGGING
FILE SEC 2.17 R26C
BOOK PAGE 24 LINE 9

15-179-00028-00-00

DRILLER'S LOG

Anschutz Drilling Company, Inc.
#1 Andregg
NW NW NW - 2-7S-26W
Sheridan County, Kansas

<u>FROM</u>	<u>TO</u>	
0	230	Clay & sand
230	665	Sand & shale
665	1260	Shale
1260	1580	Sand & shale
1580	1890	Shells & shale
1890	2050	Sand
2050	2080	Shale & red bed
2080	2262	Red bed
2262	2300	Anhydrite
2300	2620	Shale & shells
2620	3010	Shale & lime
3010	3190	Shale
3190	3270	Shale & lime
3270	3344	Shale
3344	3420	Sand, lime & shale
3420	3568	Shale & lime
3568	3675	Sand & lime
3675	3750	Lime
3750	3790	Shale & lime
3790	3825	K.C. Lime
3825	3955	Lime
3955	4037	Lime & sand
4037	4273	Shale & lime
4273	4314	Chert
4314	4391	Lime, shale & chert
4391	4427	Viola dolomite & chert
4427	4462	Viola shale & chert
4462	4472	Arbuckle
	4472	TOTAL DEPTH
		D&A

COMMENCED: 5-22-52

COMPLETED: 6-8-52

CASING RECORD

Set 8-5/8" surface casing at 227 feet with 150 sacks cement and 1 sack calcium chloride

ELEVATION: 2598 RB

TOPS

- Anhydrite 2264
- Heebner 3747
- Lansing 3782
- Base/Kansas City 3996
- Conglomerate 4273
- Mississippi Chert 4285
- Mississippi Lime 4317
- Viola 4367
- Arbuckle 4462

STATE OF KANSAS

COUNTY OF SEDGWICK

I hereby affirm that the foregoing is a true and correct copy of the log of Anschutz Drilling Company, Inc., #1 Andregg, located NW NW NW of Section 2-7S-26W, Sheridan County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY:

Leon L. Mehler
Leon L. Mehler

Subscribed and sworn to before me this 12th day of June, 1952.

Jacqueline Kinnear
Notary Public

My commission expires: May 2, 1956.

PLUGGING
FILE REC 2 T 7 R 26W
DATE 6-22-52 PAGE 9

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1952
CONSERVATION DIVISION
Wichita, Kansas

6-17-52